

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

1

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

\*\*\*\*\*

PRIME CONTRACTORS SHALL NOTIFY KDOT OF THEIR  
INTENT TO BID BY IDENTIFYING THEMSELVES AS A BID HOLDER

\*\*\*\*\*

525022121        STATE PROJECT NO:    U024-023 KA 6793-01                            DBE GOAL:            3.5%  
                    WORKING DAYS: 40    COMPLETION DATE:  
                    COUNTY: DOUGLAS  
                    TRAFFIC SIGNAL. US-24/US-40/US-59. (TEE PEE JCT) AT CR 1800 IN DG CO. LGTH IS  
                    0.001 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	TRAFFIC SIGNAL
1.00	LS	RADAR DETECTION SYSTEM
4.00	EACH	VIBRATION MITIGATOR
121.69	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
186.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
36.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
578.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
43.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
1,076.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
65.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
5.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
1,161.00	LNFT	PAVEMENT MARKING REMOVAL

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025  
TIME: 10:32am

LETTING DATE: February 19, 2025

525022131 STATE PROJECT NO: 052 N 0772-01 DBE GOAL: 1.5%  
 WORKING DAYS: CCD COMPLETION DATE: 3/2/26  
 COUNTY: LEAVENWORTH  
 GRADING, BRIDGE AND SURFACING. 158TH ST FR SHERIDAN PL TO PARALLEL RD  
 AND PARALLEL RD FR E OF 159TH ST TO 156TH ST IN BASEHOR IN LV CO. LGTH IS  
 0.97 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
11,026.00	CUYD	COMMON EXCAVATION (URB)
2,115.00	CUYD	ROCK EXCAVATION
1,720.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-3-3)
8,163.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-3-3)
1.00	MGAL	WATER (GRADING) (SET PRICE)
27,799.00	SQYD	SALVAGED TOPSOIL
531.00	SQYD	RIPRAP (HEAVY STONE)
741.00	SQYD	RIPRAP (HEAVY STONE) (1/4 TON)
2.00	EACH	ADJUSTMENT OF MANHOLES
26.00	EACH	INLET (CURB)
2.00	EACH	INLET (AREA)
31.00	TON	AGGREGATE DITCH LINING ( 6")
2,110.00	LNFT	STORM SEWER (15") (RCP)
405.00	LNFT	STORM SEWER (18") (RCP)
262.00	LNFT	STORM SEWER (24") (RCP)
17.00	LNFT	STORM SEWER (30") (RCP)
213.00	LNFT	STORM SEWER (36") (RCP)
98.00	LNFT	STORM SEWER ( 1.5 SQ.FT.) (RCPHE)
2,283.00	SQYD	SIDEWALK CONSTRUCTION ( 4") (AE)
993.00	SQYD	SIDEWALK CONSTRUCTION ( 6") (AE)
222.00	SQYD	SIDEWALK RAMP
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
626.00	CUYD	AGGREGATE FOR BLANKET UNDERDRAINS
701.00	LNFT	6" PIPE UNDERDRAINS (K)
8,373.00	LNFT	6" PIPE UNDERDRAINS (H)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
3.00	EACH	MONUMENT BOX
647.00	CUYD	FLOWABLE FILL (LOW STRENGTH)
1,808.00	SQYD	AGGREGATE BASE (AB-3) ( 4")
230.00	LNFT	HANDRAIL (METAL) (3'- 6")
584.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
187.00	LBS.	TEMPORARY SEED (RYEGRASS-ANNUAL)
29.00	LBS.	SOIL EROSION MIX
90.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
691.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE G)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LNFT	TEMPORARY BERM (SET PRICE)
85.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
28.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
2.00	EACH	TEMPORARY STREAM CROSSING
108.00	LNFT	BIODEGRADABLE LOG (20")
5,742.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
48.00	EACH	SWPPP INSPECTION
48.00	EACH	WATER POLLUTION CONTROL MANAGER
3,357.00	LBS.	MULCHING TACKING SLURRY
7.50	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
248.70	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
29,750.00	LBS.	REINFORCING STEEL (GRADE 60)
1,570.00	CUYD	CLASS III EXCAVATION (RCB)
76.00	CUYD	FOUNDATION STABILIZATION
98.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
233.80	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
37,030.00	LBS.	REINFORCING STEEL (GRADE 60)
710.00	CUYD	CLASS III EXCAVATION (RCB)
69.00	CUYD	FOUNDATION STABILIZATION
98.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
9,610.00	LNFT	CURB AND GUTTER, COMBINED (AE)
208.00	SQYD	CONCRETE PAVEMENT ( 6" UNIFORM) (AE) (PLAIN)
384.00	SQYD	CONCRETE PAVEMENT ( 8" UNIFORM) (AE) (PLAIN)
1.00	EACH	CONCRETE CORE (SET PRICE)
8,352.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
18,986.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
507.00	SQYD	MILLING
4.00	TON	SURFACING MATERIAL (AB-3)
317.00	LNFT	FENCE (BARBED WIRE)
4.00	EACH	POSTS (END) (BARBED WIRE)
159.00	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
294.00	LNFT	SIGN POST (1-3/4" PERFORATED SQUARE STEEL TUBE)
21.00	EACH	SIGN POST FOOTING ( 1-3/4" PERFORATED SQUARE STEEL TUBE)
1.00	LS	SIGN (REMOVE AND RESET)
737.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 4")
66.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
10,501.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
168.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
560.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
15.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
1.00	LS	FLASHING BEACON SYSTEM
1.00	LS	ELECTRIC LIGHTING SYSTEM
2,103.00	SQYD	SOD (FESCUE) (STRIPS)
612.00	LBS.	SEED (FESCUE) (TALL TURF TYPE BLEND)
3.40	LBS.	SEED (MIX 1)
1.00	LS	FURNISHING AND PLANTING PLANT MATERIALS

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
6,630.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
6,100.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
4,510.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
2,920.00	EADA	WORK ZONE BARRICADES (PEDESTRIAN)
6,360.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
800.00	EADA	PORTABLE CHANGEABLE MESSAGE SIGN
16.00	EACH	WORK ZONE SIGN (SPECIAL) (16.25 SQ.FT. & LESS)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022141      STATE PROJECT NO:    K177-081 KA 7660-01      DBE GOAL:      1.0%  
 WORKING DAYS: 55    COMPLETION DATE:  
 COUNTY: RILEY  
 MILLING AND HMA OVERLAY. K-177. FR GE/RL CL N END OF ASPHALT IN RL CO.  
 LGTH 6.915 MI. TIED TO KA 7659-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
22,480.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-28)
13,662.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22) (SHOULDER)
36,142.00	TON	QUALITY CONTROL TESTING (HMA)
71.00	TON	EMULSIFIED ASPHALT (SS-1HP)
273.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
334,697.00	SQYD	MILLING
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
62.90	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
730.20	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (8')(TYPE I)
10.00	EACH	PAVEMENT MARKING (TEMP) (SYMBOL) (TYPE I)
1,364.40	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
92,488.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
7,445.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
67,804.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6")
391.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
10.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022151 STATE PROJECT NO: K030-099 KA 3920-01 DBE GOAL: 0.0%  
 WORKING DAYS: 65 COMPLETION DATE:  
 COUNTY: WABAUNSEE  
 GRADING, BRIDGE AND SURFACING. K-30; BR (070) (DRAINAGE DITCH) LOC 1.22 MI  
 N OF THE 1-70/K-30 JCT IN WB CO. LGTH IS 0.044 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
257.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
92.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
139.00	CUYD	ROCK EXCAVATION
142.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
179.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
414.00	SQYD	SALVAGED TOPSOIL
215.00	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
5.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
46.50	LBS.	TEMPORARY FERTILIZER (15-30-15)
34.10	LBS.	SOIL EROSION MIX
1,500.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
30.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
500.00	SQYD	GEOTEXTILE (EROSION CONTROL)
500.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
107.70	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
71.20	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
282.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
2,090.00	LBS.	REINFORCING STEEL (GRADE 60)
42,310.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
110.00	CUYD	CLASS III EXCAVATION (RCB)
56.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
490.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
533.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1,200.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
1,200.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
2,800.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
2,000.00	EADA	CHANNELIZER (PORTABLE)
2,400.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
46.00	EACH	WORK ZONE SIGN (SPECIAL) (16.25 SQ.FT. & LESS)
6.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022161 STATE PROJECT NO: K005-105 KA 6826-01 DBE GOAL: 5.5%  
 WORKING DAYS: CCD COMPLETION DATE: 5/1/26  
 COUNTY: WYANDOTTE  
 GRADING, BRIDGE AND SURFACING. K5: BR 193 OVER UP RR AND LEVEE RD LOC  
 0.52 MI W OF US-69 IN WY CO. LGTH IS 0.169 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1,500.00	HOUR	TRAINEES HIGHWAY CONSTRUCTION (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
1.00	LS	CLEARING AND GRUBBING
9.00	CUYD	COMMON EXCAVATION (URB)
114.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
843.00	CUYD	ROCK EXCAVATION
92.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
497.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
44.00	LNFT	GUARDRAIL, STEEL PLATE
1.00	EACH	INLET (GRATE)
37.00	LNFT	SLOPE DRAIN (STONE)
1.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
1.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
15.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
11.00	LBS.	SOIL EROSION MIX
399.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
2.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
17.00	LNFT	BIODEGRADABLE LOG ( 9")
23.00	LNFT	BIODEGRADABLE LOG (12")
137.00	LNFT	BIODEGRADABLE LOG (20")
17.00	LNFT	FILTER SOCK (12")
103.00	LNFT	FILTER SOCK (18")
500.00	SQYD	GEOTEXTILE (EROSION CONTROL)
103.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
32.00	CUYD	CLASS III EXCAVATION
1,684.60	CUYD	CONCRETE (GRADE 4.0) (AE) (SA) (MPC)
36.90	CUYD	CONCRETE (GRADE 4.0) (AE)
473,830.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
6,747.00	LBS.	STRUCTURAL STEEL (A709) (GR 36)
26,002.00	EACH	WELDED STUD SHEAR CONNECTORS
183.00	LNFT	EXPANSION DEVICE (SLIDING PLATE)
910.00	SQFT	CONCRETE SURFACE REPAIR
48.00	LNFT	EPOXY RESIN CRACK REPAIR
413.00	EACH	EMBEDDED GALVANIC ANODE

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022161 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1.00	LS	BRIDGE PAINTING (CALCIUM SULFONATE / ALKYD SYSTEM)
1.00	LS	ENVIRONMENTAL PROTECTION
1.00	LS	FALSEWORK INSPECTION
115.00	SQYD	RIPRAP (REINFORCED CONCRETE) ( 4")
253.00	CUYD	FLOWABLE FILL (HIGH STRENGTH)
800.00	LNFT	FENCE (CHAIN LINK) ( 8'-0") (SPECIAL)
1.00	LS	BRIDGE DRAINAGE SYSTEM
202.00	SQYD	SUBSTRUCTURE WATERPROOFING MEMBRANE
4,679.00	SQYD	BRIDGE DECK GROOVING
1.00	LS	TEMPORARY SHORING
117.00	LNFT	CURB AND GUTTER, COMBINED (AE)
154.00	LNFT	CONCRETE SAFETY BARRIER (TYPE IV) (51")
1,211.00	SQYD	CONCRETE PAVEMENT (14" UNIFORM) (AE) (BR APP)
877.00	SQYD	CONCRETE PAVEMENT (14" UNIFORM) (AE) (NRDJ)
25.00	SQYD	CONCRETE PAVEMENT ( 4" UNIFORM) (PLAIN)
100.60	CUYD	BRIDGE APPROACH SLAB FOOTING
2,088.00	SQYD	CEMENT TREATED BASE
65.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
7,827.00	SQYD	MILLING
890.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
14.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
34.63	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
55.00	SQFT	SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)
49.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
47.00	LNFT	SIGN POST (W 6 X 9 STEEL BEAM)
2.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W 6 X 9)
2.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W 6 X 9)
12.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
2.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
5.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
2.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE RIGID "U" POST)
4,720.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
400.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 8")
105.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
3,263.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6")
1.00	LS	ELECTRIC LIGHTING SYSTEM
1.00	LS	TRAFFIC SIGNAL
44,790.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
3,450.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
8,220.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
18,290.00	EADA	CHANNELIZER (PORTABLE)
5,300.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
6.60	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
690.00	LNFT	PAVEMENT MARKING REMOVAL
3.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)



KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022161 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
1.00	LS	CRITICAL PATH METHOD SCHEDULE
1.00	LS	RAILROAD COORDINATION
1.00	LS	RAILROAD FLAGGING
		*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022242 STATE PROJECT NO: K177-064 KA 6017-01 DBE GOAL: 5.0%  
 WORKING DAYS: CCD COMPLETION DATE: 6/1/27  
 COUNTY: MORRIS  
 GRADING, BRIDGE AND SURFACING. K-177: FR APPROX 500 FT N OF S 850 RD N TO  
 VELIE ST IN COUNCIL GROVE IN MR CO. LGTH IS 3.612 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	GRANULAR BACKFILL (WINGWALLS) (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
159.00	CUYD	FOUNDATION STABILIZATION
334.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	CLEARING AND GRUBBING
57,953.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
5,626.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
21,334.00	CUYD	ROCK EXCAVATION
12,551.00	CUYD	ROCK EXCAVATION (NON-DURABLE SHALE)
1.00	MGAL	WATER (GRADING) (SET PRICE)
82,449.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
7,949.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
205,483.00	SQYD	SALVAGED TOPSOIL
513.00	CUYD	CONCRETE (GRADE 4.0) (RCB)
60,270.00	LBS.	REINFORCING STEEL (GRADE 60)
22.00	CUYD	FLY ASH SLURRY GROUT (HIGH STRENGTH)
110.00	LNFT	CROSS ROAD PIPE ( 24")
112.00	LNFT	CROSS ROAD PIPE ( 30")
74.00	LNFT	CROSS ROAD PIPE ( 36")
8.00	EACH	END SECTION ( 24")
8.00	EACH	END SECTION ( 30")
2.00	EACH	END SECTION ( 36")
112.00	LNFT	ENTRANCE PIPE ( 24")
262.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
2.00	EACH	INLET (MANHOLE) (SPECIAL)
1.00	EACH	MANHOLE (REINFORCED CONCRETE)
1,318.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
74.00	CUYD	BEDDING FOR SLOPE PROTECTION
250.00	SQYD	GEOTEXTILE FABRIC
102.00	LNFT	STORM SEWER (30") (RCP)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
320.00	LNFT	6" PIPE UNDERDRAINS (FHT)
40.00	LNFT	6" PIPE UNDERDRAINS (GK)
1.00	EACH	GUIDEPOSTS
7.10	PMP	MOWING
113.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
4.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022242 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
6,360.00	LBS.	TEMPORARY FERTILIZER (16-20- 0)
808.00	LBS.	TEMPORARY SEED (CANADA WILDRYE)
1,817.90	LBS.	TEMPORARY SEED (GRAIN OATS)
1,817.90	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
97.70	LBS.	SOIL EROSION MIX
4,771.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
2,452.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
2,466.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE F)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
2,968.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
241.00	LNFT	BIODEGRADABLE LOG ( 9")
321.00	LNFT	BIODEGRADABLE LOG (12")
6,352.00	LNFT	BIODEGRADABLE LOG (20")
241.00	LNFT	FILTER SOCK (12")
5,349.00	LNFT	FILTER SOCK (18")
3,009.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
77.00	EACH	SWPPP INSPECTION
77.00	EACH	WATER POLLUTION CONTROL MANAGER
54,538.00	LBS.	MULCHING TACKING SLURRY
121.00	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
228.00	CUYD	CLASS I EXCAVATION
651.00	CUYD	CLASS II EXCAVATION
403.00	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
246.60	CUYD	CONCRETE (GRADE 4.0) (AE)
134,660.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
42,580.00	LBS.	REINFORCING STEEL (GRADE 60)
1,175.00	LNFT	PRESTRESSED CONCRETE BEAM (NU35)
98.00	LNFT	DRILLED SHAFT ( 54") (CASED)
254.00	LNFT	CORE HOLE (INVESTIGATIVE)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
340.00	LNFT	PILES (STEEL) (HP12X53)
1.00	LS	TEMPORARY SHORING
102.00	CUYD	ABUTMENT AGGREGATE DRAIN
904.00	SQYD	BRIDGE DECK GROOVING
1,035.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
288.50	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
56,000.00	LBS.	REINFORCING STEEL (GRADE 60)
156.00	CUYD	CLASS III EXCAVATION (RCB)
56.00	CUYD	FOUNDATION STABILIZATION
264.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
330.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
46.00	CUYD	BRIDGE APPROACH SLAB FOOTING
7,838.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
247.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
20.00	TON	EMULSIFIED ASPHALT (SS-1HP)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022242 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT PAVEMENT SMOOTHNESS
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
211.00	TON	SURFACING MATERIAL (AB-3)
270.00	SQYD	AGGREGATE SHOULDER (AS-1) ( 4")
5,567.00	TON	AGGREGATE FOR SHOULDERS (AS-1)
21.00	TON	CALCIUM CHLORIDE
1.00	MGAL	WATER (AGGREGATE SHOULDERS) (SET PRICE)
2,613.00	TON	MILLING
4,685.00	TON	HMA OVERLAY (SR-19A) (PG 64-22)
12,200.00	TON	QUALITY CONTROL TESTING (HMA)
20,141.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
4,610.00	SQYD	MANIPULATION (LIME TREATED SUBGRADE)
300.00	TON	LIME
1.00	MGAL	WATER (LIME TREATED SUBGRADE) (SET PRICE)
6,114.00	TON	HMA OVERLAY (SR-19A) (PG 64-22)
13,630.00	TON	QUALITY CONTROL TESTING (HMA)
4,610.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
62.00	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
476.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
48.00	LNFT	SIGN POST (2 LB/FT "U" STEEL)
2.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
2.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
1.00	LS	SIGN (REMOVE AND RESET)
45,130.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
29,740.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
2,610.00	LBS.	FERTILIZER (13-13-13)
2,187.90	LBS.	FERTILIZER (16-20- 0)
54.70	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
6.50	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
58.70	LBS.	SEED (BUFFALO GRASS) (TREATED)
273.50	LBS.	SEED (CANADA WILD-RYE)
54.70	LBS.	SEED (INDIANGRASS) (OSAGE)
54.70	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
587.30	LBS.	SEED (RYEGRASS) (PERENNIAL)
33.90	LBS.	SEED (PRAIRIE JUNE GRASS)
254.50	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
273.50	LBS.	SEED (STERILE WHEATGRASS)
27.30	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
13.70	LBS.	SEED (TALL DROP)
587.30	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
187.70	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
281.70	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
97,440.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
11,600.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
8,120.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
23,490.00	EADA	CHANNELIZER (PORTABLE)
10,150.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022242 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
475.40	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
155.90	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
16.90	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (8')(TYPE I)
0.60	STAL	PAVEMENT MARKING (TEMP) 4" DOTTED EXTENSION (TYPE I)
22,083.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	EACH	WORK ZONE SIGN (SPECIAL) (16.25 SQ.FT. & LESS)
3.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
44.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
2.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
800.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
800.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 01/17/2025  
 TIME: 10:32am

LETTING DATE: February 19, 2025

525022414 STATE PROJECT NO: U059-002 KA 5566-01 DBE GOAL: 1.5%  
 WORKING DAYS: CCD COMPLETION DATE: 8/14/26  
 COUNTY: ANDERSON  
 GRADING AND SURFACING. US-59: ROUNDABOUT AT US-59/US-169 JCT IN AN CO.  
 LGTH IS 0.353 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
16.00	CUYD	FOUNDATION STABILIZATION
76.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
21.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1.00	LS	CLEARING AND GRUBBING
13,044.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
13,464.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
4,652.00	CUYD	ROCK EXCAVATION
15,793.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
2,038.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-0-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
44,804.00	SQYD	SALVAGED TOPSOIL
50.70	CUYD	CONCRETE (GRADE 4.0) (RCB)
5,510.00	LBS.	REINFORCING STEEL (GRADE 60)
130.00	LNFT	CROSS ROAD PIPE ( 7.0 SQ.FT.) (RCPHE)
124.00	LNFT	CROSS ROAD PIPE (12.5 SQ.FT.) (RCPHE)
200.00	LNFT	CROSS ROAD PIPE ( 48")
172.00	LNFT	ENTRANCE PIPE ( 3.0 SQ.FT.) (RCPHE)
2.00	EACH	END SECTION ( 3.0 SQ.FT.) (RCHE)
4.00	EACH	END SECTION ( 7.0 SQ.FT.) (RCHE)
4.00	EACH	END SECTION (12.5 SQ.FT.) (RCHE)
4.00	EACH	END SECTION ( 48")
213.00	TON	AGGREGATE DITCH LINING ( 6")
154.00	LNFT	SLOPE DRAIN (CONCRETE)
5.00	EACH	FLUME INLET (CONCRETE)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
6.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
1,290.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
130.40	LBS.	TEMPORARY SEED (CANADA WILD RYE)
293.40	LBS.	TEMPORARY SEED (GRAIN OATS)
293.40	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
228.60	LBS.	SOIL EROSION MIX
546.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
9,249.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
264.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE F)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022414 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
2,146.00	LNFT	BIODEGRADABLE LOG (20")
1,790.00	LNFT	FILTER SOCK (18")
1,070.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
59.00	EACH	SWPPP INSPECTION
59.00	EACH	WATER POLLUTION CONTROL MANAGER
8,802.00	LBS.	MULCHING TACKING SLURRY
19.60	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
748.00	LBS.	HYDRAULIC EROSION CONTROL PRODUCTS (TYPE C)
23,964.00	SQYD	CEMENT TREATED BASE
23,964.00	SQYD	QUALITY CONTROL TESTING (CTB)
23,964.00	SQYD	ASPHALT TREATED BASE
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
5,212.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
492.00	LNFT	CURB AND GUTTER, COMBINED (AE) (SPECIAL)
3,548.00	LNFT	CURB AND GUTTER, COMBINED (AE)
405.00	LNFT	CURB, PROTECTION ( 8.0") (AE)
16,028.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (NRDJ)
605.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (PLAIN)
4,059.00	SQYD	CONCRETE PAVEMENT (10" VARIABLE) (AE) (PLAIN)
2,544.00	SQYD	CONCRETE PAVEMENT ( 6" UNIFORM) (AE) (PLAIN)
1.00	EACH	CONCRETE CORE (SET PRICE)
1.00	EACH	CONCRETE PAVEMENT COMPOSITE PAY ADJUSTMENT
1.00	EACH	CONCRETE PAVEMENT SMOOTHNESS
458.00	TON	PAVEMENT EDGE WEDGE (ROCK)
24,615.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
23,226.00	SQYD	QUALITY CONTROL TESTING (PCCP)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
1,062.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
926.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
472.17	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
339.00	SQFT	SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)
650.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
75.00	LNFT	SIGN POST (2-1/4" PERFORATED SQUARE STEEL TUBE)
39.00	LNFT	SIGN POST (W 6 X 9 STEEL BEAM)
74.00	LNFT	SIGN POST (W10X12 STEEL BEAM)
2.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W 6 X 9)
4.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W10X12)
2.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W 6 X 9)
4.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W10X12)
44.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
135.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
6.00	EACH	SIGN POST FOOTING ( 2-1/4" PERFORATED SQUARE STEEL TUBE)
10,819.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022414 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
807.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 8")
272.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
9,400.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
2,626.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6")
109.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
1.00	LS	ELECTRIC LIGHTING SYSTEM
620.00	LBS.	FERTILIZER (13-13-13)
273.65	LBS.	FERTILIZER (15-30-15)
6.84	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
1.55	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
13.95	LBS.	SEED (BUFFALO GRASS) (TREATED)
34.21	LBS.	SEED (CANADA WILD-RYE)
6.84	LBS.	SEED (INDIANGRASS) (OSAGE)
6.84	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
139.50	LBS.	SEED (RYEGRASS) (PERENNIAL)
8.06	LBS.	SEED (PRAIRIE JUNE GRASS)
41.08	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
34.21	LBS.	SEED (STERILE WHEATGRASS)
2.39	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
1.71	LBS.	SEED (TALL DROP)
139.50	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
32.28	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
35.23	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
60,060.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
12,090.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
9,750.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
12,210.00	EADA	CHANNELIZER (FIXED)
22,620.00	EADA	CHANNELIZER (PORTABLE)
26,520.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
1,170.00	EADA	PORTABLE CHANGEABLE MESSAGE SIGN
373.20	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
129.40	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
0.60	STAL	PAVEMENT MARKING (TEMP) 4" DOTTED EXTENSION (TYPE I)
373.00	LNFT	PAVEMENT MARKING REMOVAL
16.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
1,863.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
2,988.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
2.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
4.00	EACH	IMPACT ATTENUATOR (TL-3) (TEMPORARY)
10.00	EACH	REPLACEMENT MODULES (IMPACT ATTENUATOR)

\*\*\* END OF CONTRACT \*\*\*



SUMMARY OF QUANTITIES

DATE: 01/17/2025  
TIME: 10:32am

LETTING DATE: February 19, 2025

525022424 STATE PROJECT NO: K007-006 KA 5804-01 DBE GOAL: 2.5%  
 WORKING DAYS: CCD COMPLETION DATE: 6/18/27  
 COUNTY: BOURBON  
 GRADING, BRIDGE AND SURFACING. K-7: FR CR/BB CL N TO 0.4 MI SW OF US-69 IN  
 BB CO. LGTH IS 10.394 MI. STATE TIED TO KA 5803-02.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
3,440.00	HOUR	TRAINEES HIGHWAY CONSTRUCTION (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
339.00	CUYD	FOUNDATION STABILIZATION
1,200.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	CLEARING AND GRUBBING
80,659.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
42,259.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
3.50	STA.	ERADICATION OF TRAVELED WAY
46,340.00	CUYD	ROCK EXCAVATION
110,231.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
40,545.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
414,749.00	SQYD	SALVAGED TOPSOIL
109,210.00	LBS.	REINFORCING STEEL (GRADE 60)
126.00	LNFT	CROSS ROAD PIPE ( 24") (RCP)
24.00	LNFT	CROSS ROAD PIPE ( 30") (RCP)
292.00	LNFT	CROSS ROAD PIPE ( 36") (RCP)
704.00	LNFT	CROSS ROAD PIPE ( 3.0 SQ.FT.)
32.00	LNFT	ENTRANCE PIPE ( 24")
12.00	LNFT	ENTRANCE PIPE ( 36")
1,102.00	LNFT	ENTRANCE PIPE ( 3.0 SQ.FT.)
2,573.00	SQYD	RIPRAP (LIGHT STONE) (100 LB)
33.00	EACH	GUIDEPOSTS
1.00	EACH	MANHOLE (6') (TYPE II)
7.00	EACH	END SECTION ( 24")
2.00	EACH	END SECTION ( 30")
7.00	EACH	END SECTION ( 36")
66.00	EACH	END SECTION ( 3.0 SQ.FT.)
918.50	CUYD	CONCRETE (GRADE 4.0) (RCB)
1,162.00	LNFT	4" PIPE BASEDRAINS (F)
401.00	LNFT	4" PIPE BASEDRAINS (G)
196.00	LNFT	4" PIPE UNDERDRAINS (F)
7.00	LNFT	4" PIPE UNDERDRAINS (G)
14.00	CUYD	AGGREGATE FOR BLANKET UNDERDRAINS
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
20.60	PMPS	MOWING

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
234.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
12,530.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
1,623.40	LBS.	TEMPORARY SEED (CANADA WILD RYE)
3,652.70	LBS.	TEMPORARY SEED (GRAIN OATS)
3,652.70	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
259.90	LBS.	SOIL EROSION MIX
10,546.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
899.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
256.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
153.00	LNFT	BIODEGRADABLE LOG ( 9")
204.00	LNFT	BIODEGRADABLE LOG (12")
18,790.00	LNFT	BIODEGRADABLE LOG (20")
153.00	LNFT	FILTER SOCK (12")
15,882.00	LNFT	FILTER SOCK (18")
8,722.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
93.00	EACH	SWPPP INSPECTION
93.00	EACH	WATER POLLUTION CONTROL MANAGER
112,779.00	LBS.	MULCHING TACKING SLURRY
243.50	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
230.50	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
174.90	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
448.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
3,750.00	LBS.	REINFORCING STEEL (GRADE 60)
111,480.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
92.00	CUYD	FOUNDATION STABILIZATION
104.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
833.10	CUYD	CLASS III EXCAVATION (RCB)
139.30	CUYD	CONCRETE (GRADE 4.0) (RCB)
35.10	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
125.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
5,430.00	LBS.	REINFORCING STEEL (GRADE 60)
19,970.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
37.00	CUYD	FOUNDATION STABILIZATION
178.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
33.00	CUYD	CONCRETE (GRADE 4.0) (RCB)
14.00	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
67.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1,210.00	LBS.	REINFORCING STEEL (GRADE 60)
6,770.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
17.00	CUYD	FOUNDATION STABILIZATION
24.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
54.40	CUYD	CONCRETE (GRADE 4.0) (RCB)
22.80	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
105.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1,880.00	LBS.	REINFORCING STEEL (GRADE 60)
11,050.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
25.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
50,237.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
3,765.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
15,611.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
97,217.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
36,159.00	SQYD	AGGREGATE SHOULDER (AS-1) ( 6")
40.00	TON	CALCIUM CHLORIDE
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
13,716.00	TON	MILLING
13.00	TON	SURFACING MATERIAL (AB-3)
1,301.00	TON	SURFACING MATERIAL (SA-1 OR SA-X)
54,002.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
105.00	TON	EMULSIFIED ASPHALT (SS-1HP)
779.25	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
1,330.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
120.00	LNFT	SIGN POST (2 LB/FT "U" STEEL)
9.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
110,395.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
329.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 8")
61,138.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
247.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
14.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
9.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
7,500.00	LBS.	FERTILIZER (13-13-13)
3,683.00	LBS.	FERTILIZER (15-30-15)
92.10	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
18.80	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
168.80	LBS.	SEED (BUFFALO GRASS) (TREATED)
460.40	LBS.	SEED (CANADA WILD-RYE)
92.10	LBS.	SEED (INDIANGRASS) (OSAGE)
92.10	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
1,687.50	LBS.	SEED (RYEGRASS) (PERENNIAL)
97.50	LBS.	SEED (PRAIRIE JUNE GRASS)
526.30	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
460.40	LBS.	SEED (STERILE WHEATGRASS)
32.20	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
23.00	LBS.	SEED (PRAIRIE DROPSEED)
1,687.50	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
409.10	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
473.90	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
355,730.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
87,580.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
81,380.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
67,430.00	EADA	CHANNELIZER (PORTABLE)
62,000.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)

## SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1,550.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
428.50	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
140.20	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
980.00	LNFT	PAVEMENT MARKING REMOVAL
2.00	EACH	WORK ZONE SIGN (SPECIAL) (16.25 SQ.FT. & LESS)
10.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022434

STATE PROJECT NO: K007-019 KA 5803-02  
 WORKING DAYS: CCD COMPLETION DATE: 6/18/27  
 COUNTY: CRAWFORD

DBE GOAL: 2.0%

GRADING, BRIDGE AND SURFACING. K-7: FR 0.962 MI N OF W 700TH AVE TO BB CL  
 IN CR CO. LGTH IS 2.027 MI. STATE TIED TO KA 5804-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
860.00	HOUR	TRAINEES HIGHWAY CONSTRUCTION (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
30.00	CUYD	FOUNDATION STABILIZATION
70.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	CLEARING AND GRUBBING
29,996.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
3,221.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
3,042.00	CUYD	ROCK EXCAVATION
280.00	CUYD	ROCK EXCAVATION (NON-DURABLE SHALE)
21,123.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
9,051.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
96,731.00	SQYD	SALVAGED TOPSOIL
60.10	CUYD	CONCRETE (GRADE 4.0) (RCB)
17.50	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
2,890.00	LBS.	REINFORCING STEEL (GRADE 60)
6,340.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
568.00	LNFT	CROSS ROAD PIPE ( 24") (RCP)
120.00	LNFT	CROSS ROAD PIPE ( 48") (RCP)
210.00	LNFT	CROSS ROAD PIPE ( 3.0 SQ.FT.)
354.00	LNFT	ENTRANCE PIPE ( 3.0 SQ.FT.)
535.00	SQYD	RIPRAP (LIGHT STONE) (100 LB)
1.00	EACH	INLET (MANHOLE) (SPECIAL)
116.00	CUYD	BEDDING FOR SLOPE PROTECTION
535.00	SQYD	GEOTEXTILE FABRIC
16.00	EACH	END SECTION ( 24") (RC)
1.00	EACH	END SECTION ( 48") (RC)
20.00	EACH	END SECTION ( 3.0 SQ.FT.)
363.00	LNFT	4" PIPE BASEDRAINS (F)
109.00	LNFT	4" PIPE BASEDRAINS (G)
84.00	LNFT	4" PIPE UNDERDRAINS (F)
30.00	LNFT	4" PIPE UNDERDRAINS (G)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
2.00	PMPs	MOWING
61.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
10.00	CUYD	AGGREGATE FOR BLANKET UNDERDRAINS
10.00	EACH	GUIDEPOSTS
94.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
2,477.00	LBS.	TEMPORARY FERTILIZER (15-30-15)

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525022434 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
318.00	LBS.	TEMPORARY SEED (CANADA WILDRYE)
715.50	LBS.	TEMPORARY SEED (GRAIN OATS)
715.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
67.10	LBS.	SOIL EROSION MIX
1,576.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1,389.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
398.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
2,566.00	LNFT	BIODEGRADABLE LOG (20")
2,545.00	LNFT	FILTER SOCK (18")
65.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
23.00	EACH	SWPPP INSPECTION
23.00	EACH	WATER POLLUTION CONTROL MANAGER
21,465.00	LBS.	MULCHING TACKING SLURRY
49.50	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
103.40	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
54.60	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
239.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1,950.00	LBS.	REINFORCING STEEL (GRADE 60)
27,490.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
239.10	CUYD	CLASS III EXCAVATION (RCB)
50.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
8,935.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
881.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
3,009.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	TON	QUALITY CONTROL TESTING (HMA)
16,134.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
6,865.00	SQYD	AGGREGATE SHOULDER (AS-1) ( 6")
26.00	TON	CALCIUM CHLORIDE
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
2,487.00	TON	MILLING
19.00	TON	EMULSIFIED ASPHALT (SS-1HP)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
99.00	TON	SURFACING MATERIAL (AB-3)
326.00	TON	SURFACING MATERIAL (SA-1 OR SA-X)
148.25	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
216.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
23.00	LNFT	SIGN POST (2 LB/FT "U" STEEL)
21,004.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
17,097.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
1,440.00	LBS.	FERTILIZER (13-13-13)
744.00	LBS.	FERTILIZER (15-30-15)
18.60	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
3.60	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)

## SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022434 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
32.40	LBS.	SEED (BUFFALO GRASS) (TREATED)
93.00	LBS.	SEED (CANADA WILD-RYE)
18.60	LBS.	SEED (INDIANGRASS) (OSAGE)
18.60	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
324.00	LBS.	SEED (RYEGRASS) (PERENNIAL)
18.70	LBS.	SEED (PRAIRIE JUNE GRASS)
104.00	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
93.00	LBS.	SEED (STERILE WHEATGRASS)
6.50	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
4.70	LBS.	SEED (PRAIRIE DROPSEED)
324.00	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
80.40	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
96.20	LBS.	SEED (NATIVE WILDFLOWER MIX 1)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525022454

STATE PROJECT NO: K146-019 KA 6788-01

DBE GOAL: 0.0%

WORKING DAYS: 20 COMPLETION DATE:

COUNTY: CRAWFORD

GRADING AND SURFACING. K-146; LOC 1.1 MI. E OF THE NO/CR CL IN CR CO. LGTH IS 0.026 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MOBILIZATION (DBE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
69.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
562.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
67.00	CUYD	ROCK EXCAVATION
492.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
22.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
67.00	SQYD	GEOTEXTILE FABRIC
4.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
66.00	LBS.	TEMPORARY FERTILIZER (13-13-13)
36.30	LBS.	SOIL EROSION MIX
1,504.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
103.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE F)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
57.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
163.00	LNFT	BIODEGRADABLE LOG (20")
122.00	LNFT	FILTER SOCK (18")
122.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
152.00	LNFT	CROSS ROAD PIPE ( 72") (RCP)
4.00	EACH	END SECTION ( 72") (RC)
160.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
368.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
5.56	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
17.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
4,140.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
450.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
360.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
600.00	EADA	CHANNELIZER (PORTABLE)
750.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

\*\*\* END OF CONTRACT \*\*\*



SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525024141

STATE PROJECT NO: 066 C 5287-01

DBE GOAL:

0.0%

WORKING DAYS: 105 COMPLETION DATE:

COUNTY: NEMAHA

GRADING AND BRIDGE. BR OVER STREAM LOC 0.5 MI S AND 1.5 MI E OF KELLY IN NM CO. LGTH IS 0.090 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
1,534.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
472.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
48.00	CUYD	SLOPE PROTECTION (SHOT ROCK)
48.00	TON	AGGREGATE DITCH LINING ( 6")
158.00	SQYD	GEOTEXTILE FABRIC
34.00	LNFT	ENTRANCE PIPE ( 24")
2.00	EACH	END SECTION ( 24")
150.00	LNFT	GUARDRAIL, STEEL PLATE
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
374.00	TON	SURFACING MATERIAL (AB-3)
3.00	EACH	GUARDRAIL END TERMINAL (SRT)
3.00	EACH	GUARDRAIL END TERMINAL (FLEAT)
30.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
22.00	LBS.	SOIL EROSION MIX
1,117.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
32.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
18.00	LNFT	BIODEGRADABLE LOG ( 9")
18.00	LNFT	BIODEGRADABLE LOG (12")
35.00	LNFT	BIODEGRADABLE LOG (20")
500.00	SQYD	GEOTEXTILE (EROSION CONTROL)
35.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
105.00	CUYD	CLASS I EXCAVATION
88.00	CUYD	CLASS II EXCAVATION
194.00	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
72.70	CUYD	CONCRETE (GRADE 4.0) (AE)
59,020.00	LBS.	REINFORCING STEEL (GRADE 60)
1,097.00	LNFT	PILES (STEEL) (HP12X53)
22.00	EACH	CAST STEEL PILE POINTS
2.00	EACH	CONTRACTOR FURNISHED PDA
287.00	CUYD	SLOPE PROTECTION (SHOT ROCK)

KANSAS DEPARTMENT OF TRASPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525024141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
125.00	SQYD	GEOTEXTILE FABRIC
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026121

STATE PROJECT NO: K177-031 KA 7659-01

DBE GOAL:

WORKING DAYS: 55 COMPLETION DATE:

COUNTY: GEARY

MILLING AND HMA OVERLAY. K-177. FR 0.994 MI S OF GE/RL CL N TO GE/RL CL IN

GE CO. LGTH 0.994 MI. TIED TO KA 7660-01

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
3,323.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-28)
1,728.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22) (SHOULDER)
5,051.00	TON	QUALITY CONTROL TESTING (HMA)
10.00	TON	EMULSIFIED ASPHALT (SS-1HP)
46,609.00	SQYD	MILLING
20.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
757.00	SQYD	HIGH FRICTION SURFACE
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
52.80	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
78.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (8')(TYPE I)
147.80	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
12,666.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
2,796.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
9,094.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6")
62.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026141

STATE PROJECT NO: 106 KA 7661-01  
 WORKING DAYS: 25 COMPLETION DATE:  
 COUNTY: STATEWIDE  
 RUMBLE STRIP. LOC 1; US-24 IN SN CO. LOC 2; US-75 IN SN CO. LOC 3; US-75 IN SN  
 AND JA CO. LOC 4 US-36 IN BR AND DP CO. LOC 5; US-36 IN DP CO. LOC 6; US-59 IN  
 AT CO. LGTH 59.5 MI.

DBE GOAL:

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
246.30	STA.	RUMBLE STRIPS (MILLED) (CONCRETE)
113.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
1,322.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
2,486.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
747.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
1,302.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026151

STATE PROJECT NO: I435-105 KA 6963-01

DBE GOAL:

WORKING DAYS: 15 COMPLETION DATE:

COUNTY: WYANDOTTE

CULVERT REPAIR. I 435. CULVERT NO.435-105-15.78 (523). LGTH 0.001 MI. TIED TO KA 6965-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	CLEARING AND GRUBBING
63.00	CUYD	FOUNDATION STABILIZATION
12.00	CUYD	CLASS III EXCAVATION
548.00	SQFT	PILES (STEEL SHEET)
260.00	LBS.	REINFORCING STEEL (GRADE 60)
40.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
14.00	EACH	WELDED STUD SHEAR CONNECTORS
30.00	EACH	DRILLING AND GROUTING
10.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
5.50	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026171

STATE PROJECT NO: I435-105 KA 6965-01  
 WORKING DAYS: CCD COMPLETION DATE: 12/19/25  
 COUNTY: WYANDOTTE  
 BRIDGE REPAIR. I-435. FR I-435/SWARTZ RD JCT NORTH TO I-435/CONNER CRK JCT  
 IN WY CO. LGTH 7.20 MI. TIED TO KA 6963-01.

DBE GOAL:

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
51.00	CUYD	ROCK EXCAVATION
1.00	LS	CLEANING EXISTING STRUCTURE
965.00	SQYD	MACHINE PREPARATION (1.50")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
965.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.50")
885.00	SQYD	BRIDGE DECK GROOVING
965.00	SQYD	CONCRETE SEALER (SILANE)
20.00	LNFT	BRIDGE CURB REPAIR
10.00	EACH	DRILLING AND GROUTING
30.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
965.00	SQYD	MACHINE PREPARATION (1.50")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
965.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.50")
885.00	SQYD	BRIDGE DECK GROOVING
965.00	SQYD	CONCRETE SEALER (SILANE)
70.00	LNFT	BRIDGE CURB REPAIR
45.00	EACH	DRILLING AND GROUTING
140.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
1,666.00	SQYD	MACHINE PREPARATION (2.50")
200.00	SQYD	AREA PREPARED FOR PATCHING
30.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,666.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")
1,548.00	SQYD	BRIDGE DECK GROOVING
16.00	SQFT	CONCRETE SURFACE REPAIR
12.00	LNFT	BRIDGE CURB REPAIR
1,607.00	SQYD	MACHINE PREPARATION (2.50")
60.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,607.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")
1,494.00	SQYD	BRIDGE DECK GROOVING
1,184.00	SQYD	MACHINE PREPARATION (2.50")
25.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,184.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")
1,088.00	SQYD	BRIDGE DECK GROOVING
1,634.00	SQYD	MACHINE PREPARATION (2.50")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,634.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")

KANSAS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LETTING DATE: February 19, 2025

DATE: 01/17/2025  
TIME: 10:32am

525026171 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1,498.00	SQYD	BRIDGE DECK GROOVING
78.00	SQFT	CONCRETE SURFACE REPAIR
1.00	LS	BRIDGE REPAIR
1,413.00	SQYD	MACHINE PREPARATION (2.50")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,413.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")
1,316.00	SQYD	BRIDGE DECK GROOVING
360.00	LNFT	EXPANSION JOINT (MEMBRANE SEALANT)
52.00	SQYD	CONCRETE PAVEMENT (12" UNIFORM) (AE) (BR APP)
92.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
30.00	SQYD	PCCP JOINT AND CRACK PATCHING (PARTIAL DEPTH)
20.00	SQYD	PCCP JOINT AND CRACK PATCHING (FULL DEPTH)
28.00	SQYD	PCCP PATCHING (FULL DEPTH) (12") (SOUND)
3,192.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
230.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 8")
1,064.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (BLACK) ( 6")
2,128.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6")
1,569.90	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
405.60	STAL	PAVEMENT MARKING (TEMP) (SOLID) (LINE MASKING TAPE)
518.20	STAL	PAVEMENT MARKING (TEMP) (BROKEN) (LINE MASKING TAPE)
2,500.00	LNFT	PAVEMENT MARKING REMOVAL
2,221.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
9,753.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
3.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
22.00	EACH	WORK ZONE SIGN (SPECIAL) (16.25 SQ.FT. & LESS)
7.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026181

STATE PROJECT NO: I635-105 KA 7191-02

DBE GOAL:

WORKING DAYS: 100 COMPLETION DATE:

COUNTY: WYANDOTTE

GUARDRAIL. I-635: N APPR OF BR 040 AND 041 OVER THE BNSF RR YARD N TO 1.36

MI N OF I-70/I-635 JCT IN WY CO. LGTH IS 2.355 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
306.00	CUYD	COMMON EXCAVATION (URB)
570.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
489.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
2,535.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
3,309.00	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
13.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
13.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
3.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
3.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
90.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
65.90	LBS.	SOIL EROSION MIX
3,015.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
5,615.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
842.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
33.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
10.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
1.00	EACH	SIGNING OBJECT MARKER (TYPE 3)

\*\*\* END OF CONTRACT \*\*\*



SUMMARY OF QUANTITIES

DATE: 01/17/2025  
 TIME: 10:32am

LETTING DATE: February 19, 2025

525026232      STATE PROJECT NO:    K056-057 KA 7384-01      DBE GOAL:  
 WORKING DAYS: 65    COMPLETION DATE:  
 COUNTY: MARION  
 BRIDGE REPAIR. K-56. BR 56-57-301.73 (045). LGTH 0.1197 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
94.00	LNFT	EXPANSION JOINT (STRIP SEAL ASSEMBLY)
6.60	CUYD	CONCRETE (GRADE 4.0) (AE)
290.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LS	BRIDGE PAINTING (ORGANIC ZINC W/ ACRYLIC SYSTEM)
19,590.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
10,480.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
176.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
28,867.00	LNFT	PAVEMENT MARKING REMOVAL
20.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026242

STATE PROJECT NO: I135-059 KA 6063-02

DBE GOAL:

WORKING DAYS: 55 COMPLETION DATE:

COUNTY: MCPHERSON

GUARDRAIL, I-635: FR THE HV/MP CL N TO 6.3 MI N OF THE HV/MP CL IN MP CO.

LGTH IS 0.063 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
56.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
1.00	MGAL	WATER (GRADING) (SET PRICE)
17.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
2,112.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
4,028.25	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
127.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
12.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
12.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
174.00	LBS.	TEMPORARY FERTILIZER (13-13-13)
95.60	LBS.	SOIL EROSION MIX
4,200.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
88.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
11.00	LNFT	SIGN POST (2 LB/FT "U" STEEL)
35.00	LNFT	SIGN POST (W10X12 STEEL BEAM)
2.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W10X12)
2.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W10X12)
16.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
12.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
1.00	LS	SIGN (REMOVE AND RESET)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026262

STATE PROJECT NO: K082-106 KA 7656-01

DBE GOAL:

WORKING DAYS: 50 COMPLETION DATE:

COUNTY: STATEWIDE

MILLING AND HMA OVERLAY. K-82; HOST. KA 7657-01 FR K-15/K-82 JCT E TO CY/RL  
 CL IN CY CO. LGTH 9.211 MI. KA 7658-01 FR CY/RL CL E TO K-82/US-77 JCT IN RL CO.  
 LGTH 1.513 MI. LGTH 10.724 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
15,636.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
15,636.00	TON	QUALITY CONTROL TESTING (HMA)
41.00	TON	EMULSIFIED ASPHALT (SS-1HP)
766.00	TON	HMA-COMMERCIAL GRADE (CLASS A) (PATCHING)
11,207.00	TON	MILLING
2,386.00	TON	PAVEMENT EDGE WEDGE (ROCK)
552.20	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
552.20	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
924.90	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
462.40	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
36,895.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
95,664.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
83.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
2,858.00	LNFT	PAVEMENT MARKING REMOVAL
3,187.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
3,187.00	TON	QUALITY CONTROL TESTING (HMA)
8.00	TON	EMULSIFIED ASPHALT (SS-1HP)
2,129.00	TON	MILLING
450.00	TON	PAVEMENT EDGE WEDGE (ROCK)
78.40	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
78.40	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
156.80	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
78.40	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
11,048.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
16,865.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
12.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025  
 TIME: 10:32am

LETTING DATE: February 19, 2025

525026313 STATE PROJECT NO: K025-077 KA 6737-02 DBE GOAL:  
 WORKING DAYS: 55 COMPLETION DATE:  
 COUNTY: RAWLINS  
 GUARDRAIL. K-25: JCT US-36/K-25 N TO THE KS/NE STLN IN RA CO. LGTH IS 0.519 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
6,000.00	SQYD	SALVAGED TOPSOIL
273.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
1,415.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
1.00	MGAL	WATER (GRADING) (SET PRICE)
1,226.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
293.00	LNFT	GUARDRAIL, STEEL PLATE
1,027.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
3,008.50	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
533.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
2.00	EACH	GUARDRAIL END TERMINAL (SRT)
2.00	EACH	GUARDRAIL END TERMINAL (FLEAT)
16.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
16.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
62.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
60.50	LBS.	SOIL EROSION MIX
6,000.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE D)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
400.00	LNFT	BIODEGRADABLE LOG (20")
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
3.20	CUYD	CONCRETE (GRADE 4.0)
1,930.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
144.00	EACH	DRILLING AND GROUTING
658.00	LNFT	FENCE (BARBED WIRE)
658.00	LNFT	FENCE (REMOVAL OF EXISTING)
736.00	LNFT	FENCE (BARBED WIRE) (TEMPORARY)
2.00	EACH	POSTS (CORNER) (BARBED WIRE)
8.00	EACH	POSTS (END) (BARBED WIRE)
142.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
12.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
6.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
1.00	LS	SIGN (REMOVE AND RESET)
1,040.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
1,200.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
160.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
4,000.00	EADA	CHANNELIZER (PORTABLE)
320.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
51.50	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
4,539.00	LNFT	PAVEMENT MARKING REMOVAL
40.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)

## SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026313 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
738.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
1,775.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
4.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026414

STATE PROJECT NO: U400-037 KA 6594-02

DBE GOAL:

WORKING DAYS: 100 COMPLETION DATE:

COUNTY: GREENWOOD

GUARDRAIL. US-400: FR THE E K-99/US-400 JCT E TO THE GW/WL CL IN GW CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
729.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
584.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
1,090.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
4,287.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
7,700.75	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
38.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
38.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
420.00	LBS.	FERTILIZER (13-13-13)
230.80	LBS.	SOIL EROSION MIX
10,253.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
1,775.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
35.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
135.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
48.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
12.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
1.00	LS	SIGN (REMOVE AND RESET)
1,500.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
2,100.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
9,000.00	EADA	CHANNELIZER (PORTABLE)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026424

STATE PROJECT NO: U160-063 KA 6958-01

DBE GOAL:

WORKING DAYS: 160 COMPLETION DATE:

COUNTY: MONTGOMERY

BRIDGE REPAIR. BR. NO. 160-63-415.43(066) ON US-160 OVER BIG HILL CREEK IN  
MG CO. LGTH 0.185 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	CURING ENVIRONMENT
1.00	LS	CLEARING AND GRUBBING
110.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
1,183.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
54.00	CUYD	ROCK EXCAVATION
1,033.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
2,582.00	SQYD	SALVAGED TOPSOIL
375.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
165.00	LNFT	SLOPE DRAIN (STONE)
31.50	CUYD	FLOWABLE FILL (HIGH STRENGTH)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
80.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
58.40	LBS.	SOIL EROSION MIX
740.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
399.00	LNFT	BIODEGRADABLE LOG (20")
299.00	LNFT	FILTER SOCK (18")
299.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
1,523.00	SQYD	BRIDGE DECK GROOVING
201.60	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
38,750.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
1,561.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (2.5")
77.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1,561.00	SQYD	MACHINE PREPARATION (2.50")
235.00	SQFT	CONCRETE SURFACE REPAIR
131.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
17.00	TON	SURFACING MATERIAL (AB-3)
416.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
136.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
1.00	LS	SIGN (REMOVE AND RESET)
5.56	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
39.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)

## SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
4.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
5,120.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
3,342.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
2.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
663.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
638.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
405.50	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
3,342.00	LNFT	PAVEMENT MARKING REMOVAL
30.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)

\*\*\* END OF CONTRACT \*\*\*



SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026434

STATE PROJECT NO: K058-106 KA 7570-01

DBE GOAL:

WORKING DAYS: 30 COMPLETION DATE:

COUNTY: STATEWIDE

MILLING AND HMA OVERLAY. HOST. K-58; KA 7571-01 - FR WCL LEROY TO CF/AN CL

IN CF CO. KA 7572-01 - FR CF/AN CL E TO JCT 169 IN AN CO. LGTH 14.720 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
8,352.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
8,352.00	TON	QUALITY CONTROL TESTING (HMA)
22.00	TON	EMULSIFIED ASPHALT (SS-1HP)
5,565.00	TON	MILLING
1,739.00	TON	PAVEMENT EDGE WEDGE (ROCK)
348.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
10,607.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
10,607.00	TON	QUALITY CONTROL TESTING (HMA)
28.00	TON	EMULSIFIED ASPHALT (SS-1HP)
7,068.00	TON	MILLING
2,412.00	TON	PAVEMENT EDGE WEDGE (ROCK)
428.80	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026515

STATE PROJECT NO: U050-078 KA 7569-01

DBE GOAL:

WORKING DAYS: 50 COMPLETION DATE:

COUNTY: RENO

MILLING AND HMA OVERLAY. US-50; FR SF/RN CL E TO SEGO RD IN RN CO. LGTH 16.831 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
30,647.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-28)
30,647.00	TON	QUALITY CONTROL TESTING (HMA)
60.00	TON	EMULSIFIED ASPHALT (SS-1HP)
1,341.00	CUYD	COVER MATERIAL (CM-L-1)
233.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
889.00	STA.	MANIPULATION (CHIP SEAL)
26,816.00	TON	MILLING
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1,055.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
889.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
187,806.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
53,690.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026616

STATE PROJECT NO: K156-028 KA 6729-01

DBE GOAL:

WORKING DAYS: 55 COMPLETION DATE:

COUNTY: FINNEY

BRIDGE REPAIR. K-156; BR 156-28-17.88 (005) OVER PAWNEE RIVER IN FI CO. LGTH 0.035 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
380.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
112.00	CUYD	ROCK EXCAVATION
7.00	CUYD	FLOWABLE FILL (HIGH STRENGTH)
4.00	EACH	FLUME INLET (CONCRETE)
88.00	LNFT	SLOPE DRAIN (CONCRETE)
176.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
18.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
17.00	LBS.	SOIL EROSION MIX
1,030.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
65.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
902.00	SQYD	MACHINE PREPARATION (0.75")
902.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.50")
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
3,711.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
86.00	EACH	DRILLING AND GROUTING
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
820.00	SQYD	BRIDGE DECK GROOVING
52.00	CUYD	BRIDGE APPROACH SLAB FOOTING
322.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
232.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
533.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
20,825.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
5,313.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
19,432.00	LNFT	PAVEMENT MARKING REMOVAL
226.50	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
5,312.00	LNFT	PAVEMENT MARKING REMOVAL
650.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
650.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
2.00	EACH	IMPACT ATTENUATOR (TL-3) (TEMPORARY)
10.00	EACH	REPLACEMENT MODULES (IMPACT ATTENUATOR)
20.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026626

STATE PROJECT NO: U050-028 KA 7462-01

DBE GOAL:

WORKING DAYS: 200 COMPLETION DATE:

COUNTY: FINNEY

PCCP PATCHING (CONCRETE). US-50; FR PCCP W OF HOLCOMB THEN E TO END OF 4- LANE IN FI CO. LGTH 8.390 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1,682.00	CUYD	ROCK EXCAVATION
6,055.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (NRDJ)
100.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
898.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (8')(TYPE I)
150.00	SQYD	PCCP JOINT AND CRACK PATCHING (PARTIAL DEPTH)
12,745.00	SQYD	PCCP PATCHING (FULL DEPTH) (10") (SOUND)
282,850.00	SQYD	GRINDING CONCRETE SURFACE
7,360.00	LBS.	POLYURETHANE (MUDJACKING)
136,528.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6") (WET RECOVERABLE)
4,770.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 8") (WET RECOVERABLE)
1,219.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
22,830.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4") (WET RECOVERABLE)
94,401.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 6") (WET RECOVERABLE)
2,274.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
294.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
7.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (THRU ARROW)
4.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE)(RAILROAD XING)
61.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
23.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
1.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE)(WHITE)MERGE LEFT ARROW
3.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE)(WHITE)MERGE RIGHT ARROW

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026636

STATE PROJECT NO: U056-029 KA 7623-01

DBE GOAL:

WORKING DAYS: 30 COMPLETION DATE:

COUNTY: FORD

HMA OVERLAY. US-56; FR 1400 FT E OF INTERS OF US-56/US-283 TO 250 FT W OF INTERS IN FO CO. LGTH 0.313 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
50.00	SQYD	AGGREGATE BASE (AB-3) ( 4")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
2,450.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-28)
2,250.00	TON	QUALITY CONTROL TESTING (HMA)
26.00	TON	EMULSIFIED ASPHALT (EMULSION BONDING LIQUID)
2,400.00	SQYD	MILLING
25.00	TON	HMA-COMMERCIAL GRADE (CLASS A) (PATCHING)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
60.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
15.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
4,000.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) ( 6")
3,900.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) ( 4")
110.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
120.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
9.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
3.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
3.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) THRU-RT ARROW

\*\*\* END OF CONTRACT \*\*\*

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026646

STATE PROJECT NO: K096-068 KA 6609-02

DBE GOAL:

WORKING DAYS: 190 COMPLETION DATE:

COUNTY: NESS

GRADING, BRIDGE AND SURFACING. K-96: FR E CL OF NESS CITY E TO THE NS/RH  
CO LN IN NS CO. LGTH IS 16.912 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
1.00	LS	CLEARING AND GRUBBING
342.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
13,545.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
940.00	CUYD	ROCK EXCAVATION
9,691.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
2,137.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
293.75	LNFT	GUARDRAIL, STEEL PLATE
2.00	EACH	GUARDRAIL END TERMINAL (SKT)
6,684.00	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
16.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
16.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
541.50	LBS.	FERTILIZER (16-20-0)
172.60	LBS.	SOIL EROSION MIX
17,484.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
4,495.00	LNFT	BIODEGRADABLE LOG (20")
3,371.00	LNFT	FILTER SOCK (18")
3,371.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
44.00	EACH	SWPPP INSPECTION
44.00	EACH	WATER POLLUTION CONTROL MANAGER
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
125.80	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
168.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
21,650.00	LBS.	REINFORCING STEEL (GRADE 60)
61.00	CUYD	CLASS III EXCAVATION (RCB)
35.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
315.90	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
51,730.00	LBS.	REINFORCING STEEL (GRADE 60)
102.00	CUYD	CLASS III EXCAVATION (RCB)
91.00	CUYD	FOUNDATION STABILIZATION
24.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
221.10	CUYD	CONCRETE (GRADE 4.0) (RCB BR)

SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026646 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
274.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
37,340.00	LBS.	REINFORCING STEEL (GRADE 60)
91.00	CUYD	CLASS III EXCAVATION (RCB)
55.00	CUYD	FOUNDATION STABILIZATION
54.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.40	SQYD	AREA PREPARED FOR PATCHING
2.00	EACH	EMBEDDED GALVANIC ANODE
1.00	LS	TEMPORARY SHORING
245.30	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
38,040.00	LBS.	REINFORCING STEEL (GRADE 60)
81.00	CUYD	CLASS III EXCAVATION (RCB)
70.00	CUYD	FOUNDATION STABILIZATION
24.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
303.70	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
47,140.00	LBS.	REINFORCING STEEL (GRADE 60)
96.00	CUYD	CLASS III EXCAVATION (RCB)
85.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
251.40	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
41,260.00	LBS.	REINFORCING STEEL (GRADE 60)
75.00	CUYD	CLASS III EXCAVATION (RCB)
62.00	CUYD	FOUNDATION STABILIZATION
76.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
481.30	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
76,890.00	LBS.	REINFORCING STEEL (GRADE 60)
136.00	CUYD	CLASS III EXCAVATION (RCB)
124.00	CUYD	FOUNDATION STABILIZATION
36.00	CUYD	GRANULAR BACKFILL
1.00	LS	TEMPORARY SHORING
2.80	CUYD	CONCRETE (GRADE 4.0) (AE)
680.00	LBS.	REINFORCING STEEL (GRADE 60)
92.00	EACH	DRILLING AND GROUTING
1,354.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
2,581.00	SQYD	AGGREGATE BASE (AB-3) ( 6")
770.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
5.70	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
526.00	LNFT	FENCE (BARBED WIRE)
16.00	EACH	POSTS (END) (BARBED WIRE)
16.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
4,280.00	EADA	WORK ZONE SIGNS ( 0 TO 9.25 SQ.FT.)
6,560.00	EADA	WORK ZONE SIGNS ( 9.26 TO 16.25 SQ.FT.)
570.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
19,100.00	EADA	CHANNELIZER (PORTABLE)

## SUMMARY OF QUANTITIES

DATE: 01/17/2025

LETTING DATE: February 19, 2025

TIME: 10:32am

525026646 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1,710.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
870.90	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
51,195.00	LNFT	PAVEMENT MARKING REMOVAL
110.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
6.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
1,913.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
5,063.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
*** END OF CONTRACT ***		