

**KANSAS DEPARTMENT OF TRANSPORTATION  
SPECIAL PROVISION TO THE  
STANDARD SPECIFICATIONS, EDITION 2015**

**SEASONAL LIMITATIONS**

To ensure that KDOT projects are completed to coincide with the maintenance and harvest operations, this Special Provision is to be included.

It is the intent that this project be completed during the first construction season after which this project is let. In order to assure the KDOT that this project will be completed during this period, the "Notice to Proceed" will be issued so that working days will elapse on or before October 1 for overlays with a nominal compacted thickness of one inch or less, and October 15 for thickness greater than one inch of the first construction season following the letting.

On projects that involve asphalt sealing in conjunction with an overlay, the weather and seasonal limitations will be in accordance with the standard specifications.

On projects that involve asphalt sealing only, the "Notice to Proceed" will be issued so that working days will elapse on or before the end of the sealing season.

To reduce the impact on the local harvest that may occur while the project is active, and to keep on schedule, implement the following when directed by the Engineer. No additional compensation or time will be granted for this work.

- For work near elevators, communicate and coordinate with the elevator operator to minimize the impact to elevator traffic;
- Communicate and coordinate with all active harvesting operations that have direct access to the project by way of field entrances;
- Reduce the length of the lane closures so that the wait time to the traveling public is no longer than 10 minutes. Early shut down may be necessary when the 10 minute wait time cannot be maintained;
- Work hours may be adjusted based on hauling practices for the area. Example: At the Contractor's option, road work may begin at sunrise, but roadway shall be open to unrestricted traffic by 3:00 PM.
- Station a flagger at side roads that fall within the active construction zone to assist waiting harvesters; and
- Station a flagger at field entrances that fall within the active construction zone to assist waiting harvesters.

Flaggers will be paid for using the bid item Flagger (Set Price).