

**KANSAS DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION TO THE
STANDARD SPECIFICATIONS, EDITION 2015**

**SECTION 902
TEMPORARY EROSION AND SEDIMENT CONTROL**

Page 900-7, subsection 902.1, delete the bid item "Mulching (Temporary)" and replace with "Mulching".

Page 900-7, subsection 902.1, delete the bid item Temporary Seeding by Lump Sum.

Page 900-9, delete subsection 902.3n.

Page 900-10, subsection 902.4, delete the eighth paragraph.

Page 900-10, subsection 902.4, delete the eighth paragraph, and delete the tenth paragraph and replace with the following:

The Engineer will measure mulching by the ton.

**SECTION 904
SEEDING**

Page 900-13, delete subsection 904.3a and replace with the following:

a. Seeding Seasons.

(1) Projects less than 1 acre (bid item "Seeding" per lump sum). Seed the area anytime of the year with the seed specified in the Contract Documents.

(2) Projects 1 acre or greater (bid item "Seed (*)" or "(Hydro)(*)" per pound). Determine the seeding season using **TABLE 904-1**.

| Type | Season |
|-------------------------------------|--|
| Cool Season Grasses | February 15 thru April 20 August 15 thru September 30 |
| Warm Season Grasses and Wildflowers | November 15 thru June 1 |

If cool season grasses are mixed with warm season grasses, seed the area during the seeding season for warm season grasses.

Seed the project during the proper seeding season to protect the finished grading. This may require seeding different parts of the project at different times or seasons. Complete permanent seeding during the first season after the grading work is finished. Complete the area once the seeding operations begin in an area.

The Environmental Scientist or Stormwater Compliance Engineer may extend the seeding season a few days in special situations depending on area and weather conditions.

Page 900-14, delete subsection 904.3e and replace with the following:

e. Seeding/Lump Sum. This item is only used on projects with less than 1 acre of seeding.

Prepare the seedbed, fertilize, seed and mulch all disturbed or cultivated areas within the right-of-way and construction easements according to **DIVISION 900**. This item includes all seeding and mulching necessary to meet stabilization requirements in **SECTION 901**, and includes both temporary and final surfaces. Multiple mobilizations may be required depending on how the Contractor pursues the work.